MYSORE DIVISION.

Notice dated 26th December 1928.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore Division, up to 3 P.M., 21st January 1929 for constructing a Middle School Building at Gundlupet. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore Division between the hours of 11 A.M. to 5 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of rupees two hundred and fifty only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a Middle School at Gundlupet" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rate should be queted for each item of work.

Abstract estimate for constructing a Middle School Building at Gundlupet.

Central Block.

Sl. No.	Particulars	No.	Quantity	Remarks
1	Earthwork excavation including filling basement ..	C.yds.	89	
2	Concrete in foundation	C.ft.	729	
3	Burnt stone in mortar for foundation 2 ft. deep ...	,,	1,297	
4	Burnt stone in clay (basement)	,,	733	
5	Burnt brick in clay (superstructure)	,,	2,646	
6	Burnt brick in chunam (arch work)	,,	88	
7	Burnt brick in chunam as per deduction ...	,,	469	
8	Burnt stone slabs dressed and fixed	S.ft.	284	
9	Teakwood door panelled shutters 1¼" frame, etc., complete.	,,	140	
10	Teakwood windows panelled shutters frame iron bars, etc., complete.	,,	119	
11	Teakwood glazed ventilators over windows ...	,,	26	
12	Teakwood wrought and put up with wood oiling ...	C.ft.	156·21	
13	Roofing with Mangalore tiles on teak reepers, nails, etc, complete.	Sqr.	28 15	
14	Ridge tiles set in mortar	R.ft.	134	
15	Valleys with teakwood planks, zinc sheets, chunam and cement gutters.	,,	51	
16	Rough plastering ½" thick well rubbed with trowel and sand screenings and pebbles pressed on the surface to get the effect of rough cast work.	Sqr.	65·32	

Sl. No.	Particulars	No.	Quantity	Remarks
17	Whitewashing as per plastering	Sqr.	65·32	
18	Silicate painting 3 coats to doors and windows ...	,,	6·48	
19	Tarring to wood work	Lump sum	Rs.	
20	Flooring with Mangalore tiles on 3" concrete bed and pointing with cement.	Sqr.	13·13	
21	Flooring with Cudapah slabs on 3" concrete bed and pointed with cement.	,,	2·82	
22	Junglewood eave boards with painting	R.ft.	218	
23	Cement pointing to basement	Sqr.	3·10	
24	Ornamental work round windows	Lump sum		
25	Chunam borders	,,	,,	
26	Clearing site and unforeseen charges	,,	,,	
27	Inscription stone	,,	,,	
28	Finials	No.	3	
29	Pendents	,,	6	
30	Cutting □ (rectangular) shaped stone pillars ...	,,	8	
31	Perforated brick work	,,	6	

Abstract estimate for constructing a Middle School at Gundlupet for one wing (one room at rear).

No.	Particulars	Per	Quantity	Remarks
1	Earthwork excavation and refilling in basement ...	C.yds.	26	
2	Concrete in foundation	C.ft.	212	
3	Burnt stone in mortar for foundation	,,	367	
4	Burnt stone in clay basement	,,	224	
5	Burnt brick in clay superstructure	,,	802	
6	Do in chunam arch work	,,	17	
7	Do as per deductions above	,,	72	
8	Burnt stone slabs 6" nicely dressed and fixed ...	S.ft.	76	
9	Teakwood wrought and put up with oiling ...	C.ft.	43·23	
10	Roofing with Mangalore tiles over teak reepers ...	Sqr.	7·06	
11	Ridge tiles set in mortar	R.ft.	23	
12	Rough plaster one coat ½" thick well rubbed with trovel and pressed with pebbles.	Sqr.	18·61	
13	White and colour washing inside and outside as per plastering.	,,	18·61	
14	Perforated brick work	Each	4	
15	Flooring with Cudapah slabs on 3" concrete bed with cement pointing.	Sqr.	·64	
16	Tarring wood work	Lump sum		
17	Flooring with Mangalore tiles on 3" concrete bed with cement pointing.	Sqr.	3·07	
18	Junglewood eave board with painting ...	R.ft.	104	
19	Cement pointing to basement	Sqr.	·96	
20	Ornamental work such as string course with smooth plaster 4" wide at top pillasters above, etc.	Lump sum		
21	Chunam border over roof at ends	R.ft.	50	
22	Clearing site and unforeseen charges	Lump sum		
23	Cutting V in stone pillars	Nos.	2	
24	Finials at ends	,,	2	
25	Pendents	,,	4	

Abstract estimate for constructing Middle School at Gundlupet.
Compound wall at rear of Building.

Sl. No	Particulars of work	No.	Dimensions	Remarks
1	Earthwork excavation	C yds.	11	
2	Concrete foundation one foot deep	C.ft.	99	
3	Stone mortar foundation 2' deep	,,	199	
4	Stone in clay basement	,,	143	
5	Burnt brick in clay superstructure	,,	283	
6	Burnt stone slabs dressed and fixed	S.ft.	18	
7	Plastering complete with chunam one coat rubbed with trowel, complete	Sqr.	6·79	
8	Whitewashing as per plastering	,,	6·79	
9	Cement pointing basement	,,	1·72	
10	Burnt brick in chunam with coping studded with glass pieces over.	R.ft.	58	
11	Wrought iron gate way with iron wheels, etc., painting, complete.	S.ft.	52	

N. G. KRISHNA IYENGAR,
Executive Engineer.

SHIMOGA DIVISION.

Notice dated 18th December 1928.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Shimoga Division, up to 15th January 1929, for constructing a Musafirkhana at Chandragutty, Sorab Taluk. An approximate estimate of quantities is given below These quantities are not guaranteed. The work should be completed by the end of June 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga, between the hours of 11 A.M. to 5 P.M. on the office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. 250 in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for constructing a Musafirkhana at Chandragutty, Sorab Taluk," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Shimoga Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.